BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41734

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work:Improvements Roads And Drains and Providing Covering Slabs at Srinidhi Layout Vaishnavai Layout Sai Garden Kamat Layout and Surrounding areas in Ward No 11 Kuvempunagara in Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Abbu Sambasiva Reddy ( )	
				In Figures	In Words
1	266.85	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	150.0	Rupees One Hundred Fifty Only
2	891	Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	100.0	Rupees One Hundred Only
3	94.45	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	742.0	Rupees Seven Hundred Forty Two Only
4	528	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	850.0	Rupees Eight Hundred Fifty Only
5	1.8	Providing and laying Plain cement concrete of mix 1:3:6 with with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days etc complete as per specifications and directions of engineer in charge of the work	Cum	5000.0	Rupees Five Thousand Only
6	6.48	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5500.0	Rupees Five Thousand Five Hundred Only
7	10.8	Providing ruled pointing 20 mm deep to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	150.0	Rupees One Hundred Fifty Only
8	9	Providing precast slab of 250mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge	Sqm	5000.0	Rupees Five Thousand Only
9	594	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge	Sqm	1800.0	Rupees One Thousand Eight Hundred Only
10	78.6	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, for coping. Including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5700.0	Rupees Five Thousand Seven Hundred Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92